

SCOPE OF WORK:

1- DEMO ALL DASHED PARTITIONS WHERE INDICATED ON PLANS. ALL ARE NON-LOAD BEARING. PATCH & REPAIR ADJACENT REMAINING WALLS SMOOTHLY.

2- PARTIAL DEMO OF DRYWALL IN WALLS WHERE BACKING INSTALLATION IS REQUIRED AS INDICATED ON CONSTRUCTION PLAN (CHECK CONSTRUCTION PLAN).

3- REMOVE ALL EXISTING DOORS, FRAMES AND CASINGS ACCORDING TO PLAN.

4- REMOVE ALL EXISTING FLOORING OF ENTIRE APARTMENT.

5- CEILING TO BE DEMOLISHED WHERE IS NECESSARY ACCORDING TO THE NEW RCP AND LIGHTING PROPOSED. (CHECK PROPOSED RCP + LIGHTING PLAN).

6- REMOVE ALL EXISTING LIGHT FIXTURES OF ENTIRE APARTMENT.

7- POWDER ROOM - REMOVE EXISTING PLUMBING FIXTURES, MIRROR, ACCESSORIES, VANITY, TOILET, SINK, FLOORING AND WALL TREATMENT.

8- MASTER BATHROOM - REMOVE EXISTING PLUMBING FIXTURES, MIRROR, ACCESSORIES, VANITY, TOILET, BIDET, TUB, SINK, FLOORING AND WALL TREATMENT (SHOWER INCLUDED).

9- GUEST BATHROOM: REMOVE EXISTING PLUMBING FIXTURES, MIRROR, ACCESSORIES, VANITY, TOILET, SINK, FLOORING AND WALL TREATMENT (SHOWER INCLUDED).

10- LAUNDRY - REMOVE ALL EXISTING APPLIANCES, COUNTERTOPS, CABINETS, FLOORING AND WALL TREATMENT.

11- KITCHEN - REMOVE EXISTING COUNTERTOP, CABINETS, APPLIANCES, SINK, PLUMBING FIXTURES, FLOORING AND WALL TREATMENT.

12- AC VENTS TO BE RELOCATED AND REPLACED FOR NEW

13- SPRINKLERS TO BE RELOCATED AND REPLACED FOR NEW ONES (SOCIAL AREA).

S

REV: DESCRIPTION: ANDRE'S TEAM 09/15/2023 R00 ORIGINAL DRAWING ANDRE'S TEAM 09/22/2023 R01 OVERALL UPDATES

DRAWING TITLE: DEMOLITION FLOOR PLAN

DRAWN BY:

ANDRE'S TEAM

SCALE: 1/4" = 1'-0"

SHEET NO:

PROJECT NO:

October 11, 2023

DATE: